Town of Blowing Rock

Planning Board

Agenda

Thursday, October 24th, 2024

5:30 p.m.

Call to Order

Approval of Agenda

Overview of Board and General Meeting Rules

Approval of August 15, 2024 minutes

New Business

1. Conditional Rezoning Request # 2024 - 03 Pine and Laurel Townhomes

Old Business

Committee Reports

Adjournment

DRAFT

Town of Blowing Rock

Planning Board

Minutes

Thursday, September 19th, 2024

The Blowing Rock Planning and Zoning Board met on Thursday, September 19th, 2024 for their regularly scheduled meeting. Members present were Chairman Bill McCarter, Tom Barrett, Chris Squires, Brooks Mayson, Lindsay Cook, Steven Cohen, GK Naquin and Woody Hubbard. Staff members present were Planning Director Kevin Rothrock, Zoning Officer Brian Johnson and Taylor Miller.

Meeting called to order at 5:31 p.m.

APPROVAL OF AGENDA

An amendment was made to add a discussion of bylaws to the agenda after "Other Business". Then a motion was made by Member Chris Squires to approve the agenda, seconded by Member Steve Cohen. All members in favor.

APPROVAL OF MINUTES

A motion was made by Member Steve Cohen, seconded by Member Chris Squires. All members in favor.

The board discussed procedures and bylaws for the Planning Board with Mr. Rothrock and agreed on a few changes for how they would proceed with each meeting.

1. Downtown Standard Recommendations

Mr. Rothrock presented the staff report for the Downtown Standard Recommendations. A subcommittee was put together that included four Planning Board members, two Town Council members and three members of the community. The subcommittee has put a lot of effort and thought into these standards and wanted to really understand the relationship of the landscape and building height which is what they focused on first. This information and recommendation presented today is only the beginning of more recommendations to come.

It was decided that East and West Main Street are different from each other and will develop differently so they need to be considered separately. There will be a Town Center East and a Town Center West as well as a Town Center Sunset zone.

Member Chris Squires, the Chair of the Downtown Subcommittee stated that what is being presented today is not comprehensive of what they intend to do, this is just the first piece. The group wanted to get something done and get the process started for approval. There are still discussions about material and

appearance but have primarily discussed dimensions – building heights and setback requirements, which is what is being discussed tonight.

Member Squires said that the committee is fortunate to have a variety of people with different experience, passion and points of view. We all want to maintain the character of Blowing Rock and help it continue to thrive. Although there are many different backgrounds and views, there is a general goal in common, but because there are so many different views, not every recommendation is accepted by every member of the subcommittee.

One topic that was discussed heavily was the building height for Town Center East. Everyone mutually agreed on a 5-foot setback but the height was where there were disagreements. The decided height was 30 feet, but it was suggested that there be height variation in adjacent buildings. The intent was for the variance to go down and not up. The max height will be 30 feet, but an adjacent property should have a variable height not exceeding 30 feet.

Member Steve Cohen noted that Mr. John Winkler obtained measurements of all the buildings in the Town Center and there are two buildings on East Main Street that are just shy of 30 feet.

The committee decided that no wall measured from the bottom of the grade to the top of the roof can exceed 45 feet. No building facing Main Street should exceed 35 feet. If you are in Central Business on Main Street, they can not exceed 35 feet from the entrance on Main Street.

Member GK Naquin stated that he understands this is not a complete project but wants to know how each step will look and what the complete project will look like.

It was explained that building heights and setbacks were the larger areas of concern. They will discuss other aspects later. There will be separate submittals to the Town Council each time there is a recommendation. If the Town Council approves this recommendation, it will be adopted, and they will approve/deny each submittal separately.

Member GK Naquin asked about the verbiage of "local area" in relation to the type of stone used in the materials for buildings. He stated that it was an undefined term and would need to be clarified that the stone did not need to be quarried locally but just look like a stone local to this area.

Member Brooks Mayson asked about Appendix B and the graphic provided. He noted it represents a very flat lot which is not always the case in Blowing Rock. Mr. Rothrock suggested expanding the graphics and diagrams in Appendix B. The text drives the clarification more than the pictures, but we can include better pictures.

Member GK Naquin asked about shallow lots on Sunset Drive. He wondered how much building area would be left with a 15-foot setback. He specifically pointed out the two lots on the corner of Sunset Drive and Ransom Street. Mr. Rothrock answered that the setback there today is 15 feet and is still 15 feet with these recommendations today. He did point out that it is unique where the sidewalk is not on the back of the curb like other places, but they could keep the existing footprint and if they wanted to go up a story, they would need to meet the 15 foot setback requirement.

Member GK Naquin asked about outdoor seating in the 25-foot setback on Town Center West. Kevin said a temporary structure would be fine but anything permanent would need to meet the 15-foot setback.

Member Brooks Mayson asked about Appendix 10C and why it was removed. He wanted to know if anyone had considered for it to include native plants. Member Chris Squires said this was something to be looked at later.

Chairman McCarter invited anyone from the audience to speak.

Mr. Rothrock answered specific questions in relation to specific properties and how they would be affected by these recommendations.

Member Chris Squires made a motion to recommend approval of these recommendations subject to clarifying the language about stone. This was seconded by Steve Cohen. All members in favor.

2. Bylaws Discussion

Mr. Rothrock and the board agreed to make some changes to the bylaws for the Planning Board. The main part of the amendments were to the bylaws under "Meetings". All speakers will be given 3 minutes and will need to come to the podium for the benefit of the minutes for the meeting. The board will try to go over this information at the beginning of every meeting. There will also some changes to the order of the meetings.

A motion was made by Steve Cohen, seconded by Tom I	Barrett. All members in favor.
Meeting adjourned at 6:50 p.m.	
Chairman, Bill McCarter	Support Specialist, Taylor Miller

Blowing Rock Planning Board

STAFF REPORT

Project: CZ 2024-03 Conditional Rezoning from CB to CZ-CB – Pine and Laurel

Meeting Date: October 24, 2024
Applicant: Lucrum 7, LLC

Staff: Kevin Rothrock, Planning Director

REQUEST

Lucrum 7, LLC is requesting a new conditional rezoning of the Pine and Laurel hotel property to Conditional Zoning – Central Business (CZ-CB). The 0.29 -acre property is located between Pine Street and Laurel Lane and was approved for a conditional rezoning in 2021 for a 14-room hotel project. The Applicant is now proposing the construction of 8 townhomes on the property. The property is further identified by Watauga County PINs 2807-87-8611-000, and 2807-87-7474-000.

SITE PLAN

General

This site was approved for a 14-room hotel in 2021. Initially the site was graded and underground utilities installed. Once building footers were dug and poured, the ownership paused with construction. The owners wish to change plans and seek approval of an 8-unit townhome project. The proposed townhome buildings size will be about half of the hotel size.

Setbacks

The applicable street setback for Town Center is 15 feet and is measured from the back of the existing/proposed sidewalk along each street. The proposed buildings meet the required street setbacks from both Pine and Laurel.

The side setback is 5 feet and the proposed buildings meet the side setbacks.

Building Height

The maximum building height is 30 feet from the finished sidewalk elevations to the standard 15-foot setback. Beyond the 15-foot setback, the allowable building height increases incrementally for every 5 feet of additional setback. The proposed building height for both end units is 28 feet 10 inches. The building height for the next two interior units is 33 feet 10 inches. The proposed building height for the 2 middle units is 39 feet 10 inches. Based on the proposed elevations provided, all of the buildings meet the building height requirements for the Central Business district.

Architectural Design

The building materials include a board and batten siding, lap and cedar shake siding, stone veneer, architectural roof shingles and architectural stone veneer. Some metal roofing accents are planned for some shed dormers and eave overhangs.

Parking/Access

Access to the site will be through Pine Street, one-way through the site and exiting to Laurel Lane. The proposed project requires 15 parking spaces, and 15 angled spaces are provided.

Storm Water

The storm water runoff from the site will be conveyed to an onsite detention system and released to Pine Street. This system has already been installed with the previous hotel construction.

Utilities

Sewer has been connected to Pine Street. Water has been connected to Pine Street.

A hot box for the sprinkler system and backflow preventer has been installed along Laurel Lane. It has a bright silver cover that the Town is requesting be painted or changed out to a brown or green to blend in with the surroundings.

All electrical service will be provided underground.

Garbage Collection

Garbage collection will be through roll-out containers in an enclosure located on the east side of the property adjacent to Pine Street.

Landscaping

There is a significant buffer along Laurel Lane since the Town owns an area 20 feet from the back of the existing sidewalk. As part of the hotel project, the Applicant has removed the large white pines on the Town property and will replace with other trees.

Applicant Proposed Conditions


1. None

NEIGHBORHOOD MEETING

A neighborhood meeting was held at Town Hall on October 10, 2024 where the Applicant shared their vision for the property and reasons for changing from hotel to townhomes.

ATTACHMENTS

- 1. Aerial photo
- 2. Site, grading, utility, and landscape plans
- 3. Architectural elevations and floor plans



SUNSET DR	INDEX OF DRAWINGS		
	DWG. NO.	DESCRIPTION	SHEET NO.
	C-1	COVER SHEET	1 OF 5
LAUGE	C-2	EXISTING CONDITIONS	2 OF 5
HE LAUREL NOW	C-3	PRELIMINARY SITE PLAN	3 OF 5
	C-4	PRELIMINARY GRADING PLAN	4 OF 5
NAMIN ST.	C-5	PRELIMINARY LANDSCAPE PLAN	5 OF 5
MORRIS ST STORIE ST CHESTNUT			
VICINITY MAP NOT TO SCALE			

CIVIL ENGINEER:

MUNICIPAL ENGINEERING, INC. 820-B STATE FARM RD BOONE, NC 28607 (828) 262-1767

ARCHITECT:

APPALACHIAN ARCHITECTURE 703 W. KING STREET, SUITE 201 BOONE, NC 28607 (828) 265-2406

SURVEYORS:

APPALACHIAN PROFESSIONAL LAND SURVEYORS AND CONSULTANTS, PA 1480 US HIGHWAY 421 SOUTH BOONE, NC 28607 (828) 264-0290

MUNICIPAL ENGINEERING SERVICES COMPANY, PA 820-B STATE FARM RD BOONE, NC 28607 (828) 262-1767

PINE & LAUREL TOWNHOMES

CONDITIONAL ZONING PERMIT 144 PINE STREET BLOWING ROCK, NORTH CAROLINA PROJECT NO. B24065

Municipal Engineering Inc, oone, N.C. Garner, N.C.

PRELIMINARY
FOR REGULATORY REVIEW ONLY

Ву:

Professional Engineer

LEGEND		LINETYPES	LAND USE REQUIREMENTS/ CONDITIONS	STORM
© EX. POWER POLE S EX. SS MANHOLE	PROPOSED POWER POLE PROPOSED SS MANHOLE	PROPOSED WATERMAIN PROPOSED CONTOURS	SITE ZONED: CB (CENTRAL BUSINESS) PIN: 2807-87-7474-000 & 2807-87-8611-000*	1. NEW DEVEL DETENTION IN
○ EX. SS CLEANOUT⋈ EX. GATE VALVE	PROPOSED SS CLEANOUTPROPOSED GATE VALVE	——————————————————————————————————————	PROVIDED: ALLOWED: LOT AREA: = 17,143 > = NO MIN. MIN	2. THE PROPE
EX. FIRE HYDRANT EX. LIGHT POLE	PROPOSED FIRE HYDRANT PROPOSED WATER METER	——T/B——T/B—— STREAM OR CREEK TOP OF BANK ——SB——SB—— STREAM BUFFER ——TB——TB——TB—— TROUT BUFFER	LOT AREA: = 17,143	EXISTING IMP
EX. CATCH BASIN EX. DROP INLET	PROPOSED LIGHT POLE PROPOSED STORMWATER DETETION OUTLET	EXISTING WETLANDS PROPOSED DRAINAGE PIPE EXISTING STORM DRAINAGE	BUILDING HEIGHT: = 28'-39' > = 30' - 40' MAX	EXISTING PRE PROPOSED IM
EX. WATER METER EX. GUY WIRE	CONTROL STRUCTURE PROPOSED STORMWATER DRAINAGE STRUCTURE	PROPOSED SANITARY SEWER MAIN CENTERLINE	EAVE HEIGHT: = 20' < = 24' MAX NUMBER OF UNITS: = 8 RESIDENTIAL** > = 5 UNITS/AC MAX	
EX. TEST PIT EX. DRAINAGE MANHOLE	PROPOSED STORMWATER PIPE FLARED END SECTION	FENCES EXISTING WATERLINE R/W RIGHT-OF-WAY LINE	WNITS (20.35/AC) *PROPERTIES TO BE RECOMBINED	
©- EX. GAS MARKER		EAEA EASEMENTSWS	** CONDITIONAL ZONING PERMIT REQUIRED SETBACKS: 15' ALONG STREET FRONTAGES	6 ONE BEDRO
EX. WELL EX. TREE		—————————————————————————————————————	5' ALONG ADJOINING LOTS LAND USE REQUIREMENTS	2 TWO BEDRO GUEST: $\frac{1}{4}$ UNIT
EX. BUSH EX. SIGN EX. TELEPHONE PEDESTAL EX. FIBER OPTIC MARKER		EXISTING WOODS LINE ———————————————————————————————————	 REQUESTED ZONING = CZ-CB DENSITY: 20.35 UNITS PER ACRE WESTERN ROOF SLOPE OF 4:12 ON SHED DORMERS EXISTING HOT BOX TO BE PAINTED DARK GREEN 	CREDIT TOTAL

— T——T——T—— UNDERGROUND TELEPHONE LINE

----C----C---- UNDERGROUND CABLE LINE

TORMWATER MANAGEMENT/ WATERSHED

1. NEW DEVELOPMENT WILL PROVIDE UNDERGROUND STORMWATER DETENTION IN ACCORDANCE WITH THE TOWN'S ORDINANCE.

2. THE PROPERTY IS NOT WITHIN A WATERSHED.

XISTING IMPERVIOUS SURFACE AREA = 11,412 FT²
XISTING PREVIOUS TO 1993 = 7,588 FT²
ROPOSED IMPERVIOUS SURFACE AREA = 14,029 FT²

PARKING

	REQUIRED	PROVIDED
RESIDENTIAL (8 UNITS)		
ONE BEDROOM UNITS: 1 ½ PER UNIT	9	9
2 TWO BEDROOM UNITS: 2 PER UNIT	4	4
$SUEST: \frac{1}{4} UNIT : \frac{8}{4} = 2$	2	2
CREDIT		
ΓΟTAL	15	15

MUNICIPAL


MUNICIPAL


68 SHIPWASH DRIVE, GA


E & LAUREL - CONDITIONAL ZONING
PERMIT - 144 PINE STREET
LUCRUM 7 LLC
LOWING ROCK, NORTH CAROLINA


		E BY REV. DESCRIPTION	COVER SHEET	
		DATE		
ALE	:	AS	SHOWN	
TE:	BY:	09	-20-24	
WN.	BY:	SG	S J	
KD.	BY:	MF	PT	
			T NUMBER	
		D2	1065	
B24065				


1 OF 5



















SECOND FLOOR PLAN |/8"=|'-0"



















4 EXTERIOR MATERIALS






5 REAR VIEW PERSPECTIVE A-2 N.T.S.








ARCHITECTURE, PA BILL DIXON, NCARB SUITE 201 BOONE, NC 28607

828 265 2405 FAX: 828 265 2406

▲DATE:9/20/24










BLOWING ROCK NORTH CAROLINA

DRAWN BY: LB OCHECKED BY: BD

EXTERIOR ROBR











2 PERSPECTIVE FROM PINE ST. A-3

N.T.S.




















E & LAUREL TOWNHOMES

BLOWING ROCK

